



Sl. No.	Quantity	Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
				In figures	In words
96	1.00	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required accessories such as suction, casing suction strainers sand guard Non return valve etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps (12.5 HP 25 Stage) complete as per specifications and directions of Engineer incharge of work.	No	63407.92	Rupees Sixty Three Thousand Four Hundred Seven And Paise Ninety Two Only
97	300.00	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour, charges HOM of equipments complete as per specifications and directions of Engineer incharge of work.	Mtr	452.46	Rupees Four Hundred Fifty Two And Paise Forty Six Only
98	540.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A. complete as per specifications and directions of Engineer incharge of work.	Mtr	133.01	Rupees One Hundred Thirty Three And Paise One Only
99	43.33	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset should be handed over to department including transportation (Each lenth =6.00) complete as per specifications and directions of Engineer incharge of work.	Each	92.38	Rupees Ninety Two And Paise Thirty Eight Only
100	1.00	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., complete as per specifications and directions of Engineer incharge of work.	Each	317.04	Rupees Three Hundred Seventeen And Paise Four Only
101	30.00	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A complete as per specifications and directions of Engineer incharge of work.	Mtr	147.39	Rupees One Hundred Forty Seven And Paise Thirty Nine Only
102	30.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct complete as per specifications and directions of Engineer incharge of work.	Mtr	11.34	Rupees Eleven And Paise Thirty Four Only
103	25.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete as per specifications and directions of Engineer incharge of work.	Mtr	89.23	Rupees Eighty Nine And Paise Twenty Three Only
104	3.00	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV complete as per specifications and directions of Engineer incharge of work.	Mtr	362.18	Rupees Three Hundred Sixty Two And Paise Eighteen Only


Contractor


Executive Engineer
Project Division
Yelahanka Zone

Quantity		Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
				In figures	In words
105	1.00	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete as per specifications and directions of Engineer incharge of work.	No.	293.94	Rupees Two Hundred Ninety Three And Paise Ninety Four Only
106	1.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, complete as per specifications and directions of Engineer incharge of work.	No	2862.80	Rupees Two Thousand Eight Hundred Sixty Two And Paise Eighty Only
107	6.00	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers complete as per specifications and directions of Engineer incharge of work.	No.	188.96	Rupees One Hundred Eighty Eight And Paise Ninety Six Only
108	2.00	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of Engineer incharge of work.	Nos	1658.05	Rupees One Thousand Six Hundred Fifty Eight And Paise Five Only
109	1.00	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete as per specifications and directions of Engineer incharge of work.	No	239.25	Rupees Two Hundred Thirty Nine And Paise Twenty Five Only
110	4.00	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc complete as per specifications and directions of Engineer incharge of work.	No	109.49	Rupees One Hundred Nine And Paise Forty Nine Only
111	1.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps Group A TPN complete as per specifications and directions of Engineer incharge of work.	No	1624.04	Rupees One Thousand Six Hundred Twenty Four And Paise Four Only
112	1.00	Supplying fully automatic store delta starter unit push button type with suitable wires three contractors one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3 phase and wired offer fixing to the wooden board for motor upto 12.50 HP complete as per specifications and directions of Engineer incharge of work.	No.	6910.83	Rupees Six Thousand Nine Hundred Ten And Paise Eighty Three Only
113	67.50	Earthwork excavation for pipeline trenches including deporting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boring poles at every 100 mtrs wherever necessary as directed in th following strstructure manhole complete as per specifications and directions of Engineer incharge of work.	Cum	197.36	Rupees One Hundred Ninety Seven And Paise Thirty Six Only
114	100.00	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and includng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the exexcavation Etc., complete as per specifications and directions of Engineer incharge of work.	Rmtr	164.82	Rupees One Hundred Sixty Four And Paise Eighty Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Quantity		Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
				In figures	In words
115	67.50	Refilling the basement and pipeline treanches with seclated available earthe for trench excavation including authority condition in layers from thedi including dispensary of the sunplus earth with a heavy 200 mtrs complete as per specifications and directions of Engineer incharge of work.	Cum	64.04	Rupees Sixty Four And Paise Four Only
116	4.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of Engineer incharge of work.	Each	2225.58	Rupees Two Thousand Two Hundred Twenty Five And Paise Fifty Eight Only
117	1.00	Providing and fixing of clampset and borewell cap to the pump complete as per specifications and directions of Engineer incharge of work.	No.	472.41	Rupees Four Hundred Seventy Two And Paise Forty One Only
118	15.00	Providing and 175mm dia MS Coller etc as per specification and direction engineer in charge of the work.	Nos.	157.47	Rupees One Hundred Fifty Seven And Paise Forty Seven Only
119	15.00	Providing Heavyduty coller 50mm dia complete as per specifications and directions of Engineer incharge of work.	Nos.	157.47	Rupees One Hundred Fifty Seven And Paise Forty Seven Only
120	1.00	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) complete as per specifications and directions of Engineer incharge of work.	Nos.	3149.40	Rupees Three Thousand One Hundred Forty Nine And Paise Forty Only
121	4.00	Providing 20mm square M.S footrest and fixing in manhole Nos 232.00 with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications and directions of Engineer incharge of work.	No.s	312.92	Rupees Three Hundred Twelve And Paise Ninety Two Only
122	7.00	Providing and fixing white vitreous china clay, water closet european type (pedestal type, p-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level,P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets , 40mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design,painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications and directions of Engineer incharge of work.	Each	5619.03	Rupees Five Thousand Six Hundred Nineteen And Paise Three Only
123	5.00	Providing and fixing white vitreous china clay,flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets ,32mm C.P brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications and directions of Engineer incharge of work.	Unit	3570.29	Rupees Three Thousand Five Hundred Seventy And Paise Twenty Nine Only
124	5.00	Providing and fixing 453x357mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications and directions of Engineer incharge of work.	Unit	1287.98	Rupees One Thousand Two Hundred Eighty Seven And Paise Ninety Eight Only

Contractor


Executive Engineer
Project Division
Yelahanka Zone

Quantity		Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
				In figures	In words
125	5.00	Providing and fixing C.P brass towel rail 740mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P brass screws including cost of materials, labour complete as per specifications and directions of Engineer incharge of work.	Unit	837.87	Rupees Eight Hundred Thirty Seven And Paise Eighty Seven Only
126	8.00	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia complete as per specifications and directions of Engineer incharge of work.	Each	170.07	Rupees One Hundred Seventy And Paise Seven Only
127	132.00	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing .For Rain water pipe.complete as per specifications and directions of Engineer incharge of work. 110 mm dia	m	492.06	Rupees Four Hundred Ninety Two And Paise Six Only
128	66.30	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing .For Rain water pipe.complete as per specifications and directions of Engineer incharge of work. 160mm dia	m	967.12	Rupees Nine Hundred Sixty Seven And Paise Twelve Only
129	7.00	Constructing brick masonry inspection chamber 600x600mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 600x600mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 600x600mm complete as per specifications and directions of Engineer incharge of work.	Nos.	9625.83	Rupees Nine Thousand Six Hundred Twenty Five And Paise Eighty Three Only
130	1.00	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 2000 Litre capacity) complete as per specifications and directions of Engineer incharge of work.	Each	15482.95	Rupees Fifteen Thousand Four Hundred Eighty Two And Paise Ninety Five Only
131	6.00	Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of Engineer incharge of work.	Each	196.14	Rupees One Hundred Ninety Six And Paise Fourteen Only
132	6.00	Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of Engineer incharge of work.	Each	159.86	Rupees One Hundred Fifty Nine And Paise Eighty Six Only
133	2.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of Engineer incharge of work.	Each	380.95	Rupees Three Hundred Eighty And Paise Ninety Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Quantity		Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
				In figures	In words
134	39.40	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,) complete as per specifications and directions of Engineer incharge of work.20mm nominal OD pipes	m	266.44	Rupees Two Hundred Sixty Six And Paise Forty Four Only
135	39.40	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,) complete as per specifications and directions of Engineer incharge of work.25mm nominal OD pipes	m	332.20	Rupees Three Hundred Thirty Two And Paise Twenty Only
136	36.00	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Neutral) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper conforming to the GTP With a 6Amps plug type SP control switch shall be fixed on the existing plastic sheet / gland box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block, complete for each outlet complete as per specifications and directions of Engineer incharge of work.	Point	209.96	Rupees Two Hundred Nine And Paise Ninety Six Only
137	20.00	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Neutral) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper conforming to the GTP With a 6Amps plug type SP control switch shall be fixed on the existing plastic sheet / gland box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block, complete for each outlet complete as per specifications and directions of Engineer incharge of work.	Point	288.70	Rupees Two Hundred Eighty Eight And Paise Seventy Only
138	110.00	Concealed Conduit System - Supplying heavy gauge PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, adhesive paste etc, and running before concreting and slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary complete as per specifications and directions of Engineer incharge of work. 25mm dia, 2mm thick	Rm	55.64	Rupees Fifty Five And Paise Sixty Four Only
139	80.00	Concealed Conduit System - Supplying heavy gauge PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, adhesive paste etc, and running before concreting and slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary complete as per specifications and directions of Engineer incharge of work. 32mm dia, 2mm thick	Rm	87.13	Rupees Eighty Seven And Paise Thirteen Only


 Contractor


 Executive Engineer
 Project Division
 Yelahanka Zone

Sl. No	Quantity	Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
				In figures	In words
140	100.00	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary complete as per specifications and directions of Engineer incharge of work.19/20mm dia, 2mm thick	Mtr	53.54	Rupees Fifty Three And Paise Fifty Four Only
141	70.00	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary complete as per specifications and directions of Engineer incharge of work.25mm dia, 2mm thick	Mtr	56.69	Rupees Fifty Six And Paise Sixty Nine Only
142	40.00	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary complete as per specifications and directions of Engineer incharge of work.32mm dia, 2mm thick	Mtr	85.03	Rupees Eighty Five And Paise Three Only
143	20.00	Supplying and flush modular powder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall complete as per specifications and directions of Engineer incharge of work 1 - 3 Way.	Each	99.73	Rupees Ninety Nine And Paise Seventy Three Only
144	15.00	Supplying and flush modular powder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall complete as per specifications and directions of Engineer incharge of work 4 - 5 Way.	Each	110.23	Rupees One Hundred Ten And Paise Twenty Three Only
145	100.00	Supplying 6A flush type socket and 6 amp flush type SP switch either surface/flush mountinh in existing gang box or in 4mm thik plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wire as required as per IS 1293 and IS 3654 complete as per specifications and directions of Engineer incharge of work 6AMP 3/5 and Switch.	Each	138.57	Rupees One Hundred Thirty Eight And Paise Fifty Seven Only
146	20.00	Supplying and mounting 2 Nos, of 2 Way 6amps flush type switches either surface/flush mounted on existing gang box or in 4mm thick plastic sheet and mounted on a flusg mounted wooden box and wiring as per IS 1293 complete as per specifications and directions of Engineer incharge of work	Each	179.52	Rupees One Hundred Seventy Nine And Paise Fifty Two Only
147	10.00	Supply and fixing of bakelite D.P /socket/switch with/ without neon indicator over existing wood board or flush mounting in plastic plates/nitches as per IS 1293 and IS 3854 complete as per specifications and directions of Engineer incharge of work 16Amps Combined switch and socket with indication	No	203.66	Rupees Two Hundred Three And Paise Sixty Six Only
148	25.00	Supply and fixing of bakelite D.P /socket/switch with/ without neon indicator over existing wood board or flush mounting in plastic plates/nitches as per IS 1293 and IS 3854 complete as per specifications and directions of Engineer incharge of work Electronic stepped regulator.	No	221.51	Rupees Two Hundred Twenty One And Paise Fifty One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Quantity		Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
				In figures	In words
149	250.00	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendments complete as per specifications and directions of Engineer incharge of work 2.5sqmm.	Mtr	33.59	Rupees Thirty Three And Paise Fifty Nine Only
150	205.00	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendments complete as per specifications and directions of Engineer incharge of work 4sqmm.	Mtr	47.24	Rupees Forty Seven And Paise Twenty Four Only
151	25.00	Supplying and fixing Metal Fan Box with Round Hook complete as per specifications and directions of Engineer incharge of work	Nos	89.23	Rupees Eighty Nine And Paise Twenty Three Only
152	10.00	Supplying and fixing of Group A, regular MCB distribution boards on wall/woodboard/flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB'S single phase/ 3 phase / single door with powder coated painting made out of SWG MS enclosute complete as per specifications and directions of Engineer incharge of work 12 way SP & N.	Nos	1270.26	Rupees One Thousand Two Hundred Seventy And Paise Twenty Six Only
153	10.00	Supply and fixing miniature circuit breakers on the existing MCB distribution boards using necessary fixing materials and "C" type curve, Indicator ON/OFF energy cross -3 with as required confirming to IEC 60898 complete as per specifications and directions of Engineer incharge of work 5-32 AMPS DP.	Nos	954.27	Rupees Nine Hundred Fifty Four And Paise Twenty Seven Only
154	1.00	Supplying, fixing and wiring earth electrode for grounding conduits , I.C. cutouts and others equipments on the meter board using 40mm dia 2.90mm long buried in a pit.. the pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit ect, is to be established through GI wire of size as ISI specification 7.3.3 of IS 732 using 12mm dia bolt, nut, washers and check nuts ect... the pipe shall have 16 through holes of 122mm dia, complete as per specifications and directions of Engineer incharge of work.	No	3149.09	Rupees Three Thousand One Hundred Forty Nine And Paise Nine Only
155	35.00	Supplying and running of GI/ copper strips for grounding connections, using necessary fixing materials as required complete as per specifications and directions of Engineer incharge of work. 25 x 3mm G.I strip	Mtr	78.74	Rupees Seventy Eight And Paise Seventy Four Only
156	35.00	Supplying of feet - PVC Batten with integrated LED tube W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50/60Hz & Power factor >0.9 along with CE approved. 2 years Warranty against any manufacturing defect working under standard electrical condition. LED light fighting 1 x4'- 20/22 w complete as per specifications and directions of Engineer incharge of work.	Each	393.68	Rupees Three Hundred Ninety Three And Paise Sixty Eight Only
157	25.00	Supplying capacitor type ceiling fan complete with down rod blades shackle, canopies etc, for operation on 230 volts, 50 cycles. single phase AC supply conforming to ISS-374-1979 and with double ball bearing system complete as per specifications and directions of Engineer incharge of work.48" sweep (1200mm)	Each	2194.08	Rupees Two Thousand One Hundred Ninety Four And Paise Eight Only
158	7.00	Supply Exhaust fan if 1440 RPM of (12") size with dracket blades complete for light duty suitable to -operate on 230V 50Hz, supply complete as per specifications and directions of Engineer incharge of work.	Each	1259.76	Rupees One Thousand Two Hundred Fifty Nine And Paise Seventy Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Sl. No.	Quantity	Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
				In figures	In words
159	2.00	Supplying and Fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete, protection of Overload and Short circuit with thermal Magnetic/Microprocessed release and Earth Fault as per IS-13947. (icu =lcs) (53/4.12) complete as per specifications and directions of Engineer incharge of work. 630Amps 50kA	Each	30535.99	Rupees Thirty Thousand Five Hundred Thirty Five And Paise Ninety Nine Only
160	2.00	Supplying and Fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete, protection of Overload and Short circuit with thermal Magnetic/Microprocessed release and Earth Fault as per IS-13947. (icu =lcs) (53/4.12) complete as per specifications and directions of Engineer incharge of work. 63/100Amps 25kA	Each	6098.29	Rupees Six Thousand Ninety Eight And Paise Twenty Nine Only
161	16.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' cure, indicator ON/OFF, energy cross-3 with Short circuit breaking cappacity of 10K and complete wiring as required. Confirming to IEC 60898. (54/6.15) complete as per specifications and directions of Engineer incharge of work.40-63Amps TPN	Each	2032.41	Rupees Two Thousand Thirty Two And Paise Forty One Only
162	2.00	Supplying and fixing Trivector meter suitable for operation LT operation and CT operated meter in polycarbonate body in class 0.5accuracy as per IS 14697 and completely wired complete as per specifications and directions of Engineer incharge of work.	Each	3966.14	Rupees Three Thousand Nine Hundred Sixty Six And Paise Fourteen Only
163	2.00	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C. 50 Hz 12/24v D.C (48/6.36) complete as per specifications and directions of Engineer incharge of work.	Each	464.01	Rupees Four Hundred Sixty Four And Paise One Only
164	2.00	Supplying, fixing and wiring 50/5 to 1000/5Amps 5VA burden Current Transformer. Class 0.5 accuracy with Tape Wound (48/6.32) complete as per specifications and directions of Engineer incharge of work.	Each	755.86	Rupees Seven Hundred Fifty Five And Paise Eighty Six Only
165	30.00	Supplying of 1.1 KV LT UG cable having aluminium conductor PVC insulated, extruded inner sheathed, galvanised, steel strip (except 2Cx 10Sq.mm wire armoured) Confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheated armoured cable with specified IS-1554 Part-1:1998 & confirming to the attached GTP of GROUP-A. (62/7.4) complete as per specifications and directions of Engineer incharge of work. 3.5 core 240 sqmm	Mtr	1186.27	Rupees One Thousand One Hundred Eighty Six And Paise Twenty Seven Only
166	28.40	Supplying of 1.1 KV LT UG cable having aluminium conductor PVC insulated, extruded inner sheathed, galvanised, steel strip (except 2Cx 10Sq.mm wire armoured) Confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheated armoured cable with specified IS-1554 Part-1:1998 & confirming to the attached GTP of GROUP-A. (62/7.4) complete as per specifications and directions of Engineer incharge of work. 3.5 core 25 sqmm	Mtr	188.96	Rupees One Hundred Eighty Eight And Paise Ninety Six Only
167	30.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct. (68/7.8) complete as per specifications and directions of Engineer incharge of work.25 sqmm to 75 sqmm	Mtr	16.27	Rupees Sixteen And Paise Twenty Seven Only
168	28.40	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct. (68/7.8) complete as per specifications and directions of Engineer incharge of work.300 sqmm 400 Sqmm	Mtr	33.59	Rupees Thirty Three And Paise Fifty Nine Only
169	6.00	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.(64/7.21) complete as per specifications and directions of Engineer incharge of work.25 sqmm Long Barrel	Each	21.62	Rupees Twenty One And Paise Sixty Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Quantity	Item Name	Unit	Approved Rates of S K KESHAVAMURTHY	
			In figures	In words
170	6.00	Each	354.83	Rupees Three Hundred Fifty Four And Paise Eighty Three Only
171	6.00	Each	267.70	Rupees Two Hundred Sixty Seven And Paise Seventy Only
172	4.00	Each	520.70	Rupees Five Hundred Twenty And Paise Seventy Only
173	15.00	Mtr	11.28	Rupees Eleven And Paise Twenty Eight Only
174	15.00	Mtr	355.00	Rupees Three Hundred Fifty Five Only
175	15.00	Mtr	600.00	Rupees Six Hundred Only
176	GST @ 12%			

Handwritten signature/initials in blue ink.

Contractor

24

Handwritten signature in green ink.
 Executive Engineer
 Project Division
 Yelahanka Zone